BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2024-25/OW/WORK_INDENT5319

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/09/2024-25, Date: 19-10-2024

Name Of Work: CONSTRUCTION OF ANGANAVADI BUILDING AT JAKKUR LAYOUT IN WARD NO. 08, AMRUTHAHALLI.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. Shree Vigneshwara Enterprises, Prop. K. Narasimha	
				In Figures	In Words
1	10.89	Demolishing cement concrete manually/ by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge.	Cum	1884.00	Rupees One Thousand Eight Hundred Eighty Three and Ninety Nine Paise Only
2	19.86	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material to the appropriate disposal area as per direction of Engineer-in-charge.	Cum	546.05	Rupees Five Hundred Forty Six and Five Paise Only
3	29.53	Dismantling tile work in floors and roofs laid in cement mortar including stacking material to the appropriate disposal area as per direction of Engineer-in-charge.For thickness of tiles 10 mm to 25 mm	Sqm	54.38	Rupees Fifty Four and Thirty Seven Paise Only
4	41.75	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of Buildings & bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. Depth exceeding 1.5m, but not exceeding 3 m	Cum	293.42	Rupees Two Hundred Ninety Three and Forty One Paise Only
5	13.31	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other ppurtenances required to complete the work as per technical specifications.Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates	Cum	6784.88	Rupees Six Thousand Seven Hundred Eighty Four and Eighty Seven Paise Only
6	22.86	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	7238.03	Rupees Seven Thousand Two Hundred Thirty Eight and Three Paise Only

K. Narasimha
Signature of the Contractor

Executive Engineer

Name Of Work: CONSTRUCTION OF ANGANAVADI BUILDING AT JAKKUR LAYOUT IN WARD NO. 08, AMRUTHAHALLI.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. Shree Vigneshwara Enterprises, Prop. K. Narasimha	
				In Figures	In Words
7	24.39	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications.M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	9331.39	Rupees Nine Thousand Three Hundred Thirty One and Thirty Eight Paise Only
8	3.54	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification. All other type of structures	Tonne	101344.94	Rupees One Hundred One Thousand Three Hundred Forty Four and Ninety Four Paise Only
9	107.96	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	1484.09	Rupees One Thousand Four Hundred Eighty Four and Eight Paise Only
10	11.44	Providing Flush/ Ruled pointing: Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) after raking joints to depth nicely lining, including cost of materials, labour, curing as per specifications and as per directions of Engineer-in-charge	Sqm	288.89	Rupees Two Hundred Eighty Eight and Eighty Eight Paise Only
11	38.95	Providing 12 mm cement plaster with cement mortar 1:4 (1 cement: 4 fine sand) to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	288.89	Rupees Two Hundred Eighty Eight and Eighty Eight Paise Only
12	132.00	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-Charge	Sqm	401.04	Rupees Four Hundred One and Four Paise Only
13	162.24	Providing 20 mm cement plaster with cement mortar 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement to brick/ stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	486.01	Rupees Four Hundred Eighty Six Only
14	170.95	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge.	Sqm	113.29	Rupees One Hundred Thirteen and Twenty Eight Paise Only

Signature of the Contractor

Executive Engineer
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ರಾಯಚೂರು ವಿಭಾಗ

Name Of Work: CONSTRUCTION OF ANGANAVADI BUILDING AT JAKKUR LAYOUT IN WARD NO. 08, AMRUTHAHALLI.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. Shree Vigneshwara Enterprises, Prop. K. Narasimha	
				In Figures	In Words
15	162.24	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two coat applied @ 1.67L/10 m² over and including priming coat of exterior primer applied @ 2.20 kg/10 m²) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	197.12	Rupees One Hundred Ninety Seven and Twelve Paise Only
16	143.95	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Two coats applied on walls @ 1.25 L/10 m² over and including one coat of Special primer applied @ 0.75 L/10 m² with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (The gloss should be 50% @ 60 degree angle with 10 years life)	Sqm	179.00	Rupees One Hundred Seventy Eight and Ninety Nine Paise Only
17	43.47	Providing and laying Vitrified tiles with thickness 9-10 mm in different sizes with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	Sqm	1331.15	Rupees One Thousand Three Hundred Thirty One and Fourteen Paise Only
18	2.40	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.	Sqm	3231.00	Rupees Three Thousand Two Hundred Thirty One Only
19	6.60	Providing skirting, dadooing, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.	Sqm	1641.56	Rupees One Thousand Six Hundred Forty One and Fifty Five Paise Only
20	1.20	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/m2 including pointing the joints with white cement and matching pigment etc., complete.	Sqm	1218.99	Rupees One Thousand Two Hundred Eighteen and Ninety Eight Paise Only
21	0.18	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per specifications.	Cum	156422.65	Rupees One Hundred Fifty Six Thousand Four Hundred Twenty Two and Sixty Five Paise Only

K. Narasimha
Signature of the Contractor

Executive Engineer
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ

Name Of Work: CONSTRUCTION OF ANGANAVADI BUILDING AT JAKKUR LAYOUT IN WARD NO. 08, AMRUTHAHALLI.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. Shree Vigneshwara Enterprises, Prop. K. Narasimha	
				In Figures	In Words
22	5.67	Providing and fixing in position fully panelled Honne wood shutters for doors with stiles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and stiles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, usage charges complete as per specifications. (excluding cost of fixtures)	Sqm	8433.23	Rupees Eight Thousand Four Hundred Thirty Three and Twenty Three Paise Only
23	14.18	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	189.19	Rupees One Hundred Eighty Nine and Nineteen Paise Only
24	5.70	Providing & fixing factory made PVC Door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2 No.s of 150mm long brackets of 15x15mm M.S Square tube, the entire door frame to be reinforced with 19x19mm M.S Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufacturers specification & direction of Engineer-in-charge	Sqm	360.26	Rupees Three Hundred Sixty and Twenty Five Paise Only
25	1.58	Providing & fixing 30mm thick factory made rigid foam Panelled Door Shutters made from M.S. tube of 19 gauge thickness, size 19x19mm for stiles and 15x15mm for top & bottom rails, covered with heat moulded PVC C channel of 5mm thick sheet & 30 x 50mm wide to form stiles & 5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick 20mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, Sealed to the stiles & rails with 5x30mm PVC sheet beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75 mm Aluminium hinges.	Sqm	1799.03	Rupees One Thousand Seven Hundred Ninety Nine and Two Paise Only
26	8.64	Providing & fixing of 3-track x 2 panel sliding windows made out of multi chambered UPVC(Matching to RAL 9016) sections and with minimum TiO2 Titanium Dioxide at 6PHR with TPE(Thermo Plastic Elastomer) and lead free, gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 108mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 37mm x 58mm. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24 mm. Windows shall be provided with 6mm plain float glass, standard hardware& Multi point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm 2.5mm. Maximum possible size 419mm x 2200mm. The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made	Sqm	7628.88	Rupees Seven Thousand Six Hundred Twenty Eight and Eighty Eight Paise Only

K. Narasimha
Signature of the Contractor

Executive Engineer
ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

Name Of Work: CONSTRUCTION OF ANGANAVADI BUILDING AT JAKKUR LAYOUT IN WARD NO. 08, AMRUTHAHALLI.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. Shree Vigneshwara Enterprises, Prop. K. Narasimha	
				In Figures	In Words
27	42.15	Polyurethane based Single Component for New Surface Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU waterproofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6 kg/m2 to achieve final DFT (Dry Film Thickness) of 1mm including prime coat of epoxy primer @150 g/m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification.	Sqm	925.57	Rupees Nine Hundred Twenty Five and Fifty Seven Paise Only
28	204.12	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc.	Kg	207.32	Rupees Two Hundred Seven and Thirty One Paise Only
29	2.00	Constructing brick masonry chamber for underground C.I. inspection chamber and bends with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) C.I. cover with frame (light duty) 600X850 mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg), R.C.C. top slab with 1:1.5:3 mix (1 cement : 1.5 fine sand : 3 graded stone aggregate 20 mm nominal size), foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size), inside plastering 12 mm thick with cement mortar 1:3 (1 cement : 3 coarse sand), finished smooth with a floating coat of neat cement on walls and bed concrete etc	1 chamber	8384.52	Rupees Eight Thousand Three Hundred Eighty Four and Fifty One Paise Only
30	25.00	Supplying heavy gauge PVC conduit pipe ..... mm dia.....mm thick confirming to IS 2509 with suitable size bends, metal/PVC Junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary 25mm dia 2mm thick.	m	80.33	Rupees Eighty and Thirty Three Paise Only
31	25.00	Supplying heavy gauge PVC Conduit Pipe .... dia ..... mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering upto the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary. 25 mm dia 2 mm thick	m	81.36	Rupees Eighty One and Thirty Six Paise Only
32	4.00	Supplying and fixing PVC/metal conduit Deep junction box 25 mm deep Junction box	Each	57.67	Rupees Fifty Seven and Sixty Seven Paise Only
33	2.00	Supplying And Fixing Metal Fan Box with Round Hook.	Nos	120.50	Rupees One Hundred Twenty and Forty Nine Paise Only

K. Narasimha
Signature of the Contractor

Executive Engineer

Name Of Work: CONSTRUCTION OF ANGANAVADI BUILDING AT JAKKUR LAYOUT IN WARD NO. 08, AMRUTHAHALLI.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. Shree Vigneshwara Enterprises, Prop. K. Narasimha	
				In Figures	In Words
34	6.00	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0 sqmm (Earth wire) FRLS multi strand PVC insulated copper wire (confirming to IS-694: and latest amendments) with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/ gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. Medium point above 3m upto 6m from tapping point to out letvia switch	Point	390.33	Rupees Three Hundred Ninety and Thirty Three Paise Only
35	4.00	Supplying and wiring adopting loop system in existing PVC Conduit /casing capping using 2x1.5mm2 (Phase & Neutral) & 1x1.0 mm2 (Earth wire) FRLS multi strand PVC insulated copper wire (confirming to IS-694: and latest amendments) with a 6A flush type SP control switch shall be fixed on the existing plastic sheet/ gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outletLong point above 6m upto 10m from tapping point to out let via switch	Point	571.59	Rupees Five Hundred Seventy One and Fifty Nine Paise Only
36	30.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS- 694:2010 1 sqmm	Mtr	19.57	Rupees Nineteen and Fifty Six Paise Only
37	30.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. - 2.5 sqmm.	Mtr	43.26	Rupees Forty Three and Twenty Five Paise Only
38	4.00	Supplying 6A flush type socket and 6 A flush type SP switch either surface/flush mounting in existing gang box or in 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required as per IS 1293 and IS 3654 - 6Amps 3/5 Way	Each	151.40	Rupees One Hundred Fifty One and Thirty Nine Paise Only
39	4.00	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall - 8Way	Each	268.80	Rupees Two Hundred Sixty Eight and Eighty Paise Only
40	800.00	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches, regulators etc, and fixing on existing wooden or metal box using N.F. screws.	Sq CM	0.42	and Forty Two Paise Only
41	2.00	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293.. - Stepped Fan Regulator Two Module	Each	367.67	Rupees Three Hundred Sixty Seven and Sixty Seven Paise Only
42	15.00	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293.. -6A One Way Switch	Each	105.05	Rupees One Hundred Five and Four Paise Only

K. Narasimha
Signature of the Contractor

Executive Engineer

Name Of Work: CONSTRUCTION OF ANGANAVADI BUILDING AT JAKKUR LAYOUT IN WARD NO. 08, AMRUTHAHALLI.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. Shree Vigneshwara Enterprises, Prop. K. Narasimha	
				In Figures	In Words
43	2.00	Supplying of Ceiling Fan with Capacitor rating As per guideline of BEE 5 star rating and IS:374/79 and also comply with IS: 1709/1984 with latest amendment, Rated voltage 220 V/50 Hz, Rated power input 48 W +/- 10 %, Rated current As per IS:374/79, Rated power factor 0.9 lagging(min), Rated speed 350 +/- 10% RPM, Rated air delivery 210 +/- 10% Cubic Meter Minimum, Rated service value 4.2 CMM / W, Three Blades of blade leaf 1.05 mm thick Aluminium Alloy sheet, Class B motor insulation, Bearing Two ball bearings, Top 6202, Bottom 6201, as per IS specification, Motor winding. Temp rise Shall not exceed 75 deg C over and ambient of 40 0C by resistance method at 245 V, Insulation resistance Shall not be less than Two Mega Ohms (2M Ohms), Leakage current Should not exceed 210 Micro Amp, Power input, W& current, Air Delivery & Fan Speed as per IS:374/1979 with latest amendment, 2 year manufacturer Warranty..48" Sweep 5 Star (1200 mm)	Each	2757.04	Rupees Two Thousand Seven Hundred Fifty Seven and Four Paise Only
44	1.00	Supplying & fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.6-32 A SP	Each	427.41	Rupees Four Hundred Twenty Seven and Forty Paise Only
45	1.00	Supplying, fixing and wiring Electronic Trivector Meter (ETV) 5 to 32/63 A three phase 4 wire whole current class-1 Accuracy Energy Meter.	Each	5875.58	Rupees Five Thousand Eight Hundred Seventy Five and Fifty Seven Paise Only
46	30.00	Supplying of 1.1KV LT UG cable XPLE or heat resistant PVC Insulated PVC eatruded inner sheath armoured UG LT cable as per IS -1554(Part-1) or IS-7098 Part-1,Armouring strip thickness in average +5% and resistivity 14ohms/kms(max) as per IS -3975 4 core 16sqmm	Mtr	154.49	Rupees One Hundred Fifty Four and Forty Eight Paise Only
47	30.00	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stone pipe / on wall/ on pole as required 6 sqmm to 16 sqmm.	Mtr	12.24	Rupees Twelve and Twenty Three Paise Only
48	30.00	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete cutting road surfaces	Mtr	84.45	Rupees Eighty Four and Forty Five Paise Only
49	4.00	Supplying and fixing of class A GI pipe on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class 40mm	Nos	345.02	Rupees Three Hundred Forty Five and One Paise Only
50	1.00	Earthing : Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia	Nos	3862.13	Rupees Three Thousand Eight Hundred Sixty Two and Twelve Paise Only

K. Narasimha
Signature of the Contractor

Executive Engineer

Name Of Work: CONSTRUCTION OF ANGANAVADI BUILDING AT JAKKUR LAYOUT IN WARD NO. 08, AMRUTHAHALLI.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. Shree Vigneshwara Enterprises, Prop. K. Narasimha	
				In Figures	In Words
51	30.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall. a) 25 mm nominal dia Pipes.	m	360.26	Rupees Three Hundred Sixty and Twenty Five Paise Only
52	30.00	b) 32 mm nominal dia Pipes	m	453.16	Rupees Four Hundred Fifty Three and Fifteen Paise Only
53	1000.00	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank	l	10.20	Rupees Ten and Nineteen Paise Only
54	2.00	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	Each	3491.57	Rupees Three Thousand Four Hundred Ninety One and Fifty Six Paise Only
55	1.00	Providing and fixing white vitreous china extended wall mounting water closet of size 780x370x690 mm of approved shape including providing & fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/ 6 litre (adjustable to 4 litre/ 8 litres), including seat cover, and cistern fittings, nuts, bolts and gasket etc complete.	Each	12715.56	Rupees Twelve Thousand Seven Hundred Fifteen and Fifty Five Paise Only
56	5.00	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in Granite, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	Each	669.54	Rupees Six Hundred Sixty Nine and Fifty Three Paise Only
57	24.00	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 100 mm diameter	m	329.67	Rupees Three Hundred Twenty Nine and Sixty Seven Paise Only

K. Narasimha

Signature of the Contractor

Executive Engineer
Byrarayanapura Division
Bruhat Bengaluru Mahanagara Palike